

	MODULAR HOUSES AND CONSTI
Part	Description
G/ FLOORS ⁵	 Knauf Vidifloor, 2 – ply /2 x 10/ dry floor system – thermally insulated floor.
H/ WINDOW SYSTEMS	UPVC or Aluminium system equipped with specific closing mechanisms, double / triple glazing, up to clients criteria.
I/ ENTRANCE DOORS	Safety entrance door, up to project and client criteria.
J/ INTERIOR DOORS	<u>Veneered MDF interior doors</u> . Relevant locking systems installed in accordance with room type.
K/ ELECTRICAL	3-wire electric cable system, double insulation cables for steel-construction wiring, watertight connections throughout, switchboard, fuses and components – Schneider Electric - SIMON - JUNG etc.
L/ PLUMBING AND SEWAGE	 Plumbing – polypropylene pipes and joints for drinking water. Sewage – UPVC pipes and sealed joints – sewage ventilation installed.
M/ BATHROOMS	Bathroom equipment brands <u>Geberit</u> , <u>Grohe</u> , <u>Hansgrohe</u> , <u>Duravit</u> , <u>TRES</u>
N/ HVAC	Kitchen, sewage and bathroom ventilation piping with roof vents.
O/ Air conditioning	Brand ' <u>Mitsubishi Electric</u> '.
P/ Modular details	 Detail floor and ceiling – <u>View 1</u>, <u>View 2</u> Detail exterior wall – <u>View</u> Detail partition wall – <u>View 2</u> Detail roof – <u>View 1</u>, <u>View 2</u>